BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFED DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of the Work : Providing New Street Signage Boards and Refixing, Repainting, Rewrighting and Repairs of old Boards in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	10.00	Providing and fixing RCC name board of size 1.35xk0.60x0.04 mtrs fixed in reinforced cement concrete poles of size 0.10x0.10x2.60 mtrs in cement concrete 1:1 1/2::3 proportion using 20 mm and down size graded metal machine mixed with 10 mm dia main steel bars and 8mm dia stripes show in drawing the board shall be provided with 12 mm thick cement plaster in cement mortar 1:3 on both the side, the poles shall be 1:3:6 proportion, the board shall be fixed as per the drawing and at the place indicated by the engineering charge of the work, the cost includes excavation, cost of all materials, cost of steel, centering, transportation, charges, fixing charges etc, the work shall be carried out as per the detailed specifications, drawings and directions of the engineer in charge	Each	5184.00	
2	207.00	Providing and fixing sign board of size 60x60cm equilateral triangle using M.S sheet 5 mm thick with RCC pole of size 0.15x0.15x2.3 mtr made out of cement concrete 1:11/2:3 proportion using 20 mm and down size graded metal machine mixed with 10 mm dia main steel bars and 8 mm dia stirupps as shown in drawing, the poles shall be embedded in the ground for a depth of 0.6 mtrs with cement concrete 1:3:6 proportion, the board shall be fixed as per drawing and at the place indicated by the engineering charge of the work, the cost includes excavation, cost of all materials, cost of steel, centering, transportation charges, fixing charges etc, the work shall be carried out as per the detailed specifications, drawings and directions of the engineer in charge of the work	Each	5184.00	
3	59.62	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5m. In depth with lead upto 50m. after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	227.88	
4	59.62	Loading and unloading ofstone **aggregates / sand/ kanker/ Moorum /soil** KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 117 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M etc complete as per specifications and directions of engineer in charge of the work	cum	72.71	

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Name of the Work : Providing New Street Signage Boards and Refixing, Repainting, Rewrighting and Repairs of old Boards in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

5	20.96	Providing and laying in position plain cement concrete of **mix M20 with OPC cement @ 300 kgs, with 20mm** and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5323.32	
6	370.80	Painting lines, dashes, arrows etc, on roads in two coats on new work :- painting lines, dashes, arrows etc on roads in two coats on new work with ready mixed road marking paint conforming to IS:164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at the and traffic control etc complete as per specifications and directions of engineer in charge of the work	Sqm	108.00	
7	85000	Painting new letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification etc complete as per specifications and directions of engineer in charge of the work	Cm	0.65	

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

DTS Approved.